

SHEET NO.	SEWER SIZE (V.C.)	LOCATION	TYPE RESURFACING	REMARKS
2	8"	EASEMENT-ALLEY	DIRT (95% DMP)	A.C. ON CONC @ MARKET ST
3	"	"	"	"
4	"	"	"	"
5	"	HILLTOP DR	CL "D" CONC	(ON MARKET ST-A.C. ON CONC.
6	"	"F" ST-BNDY ST	CL "D" CONC-DIRT	"
7	"	ALLEY	CONC PAV	CONC PAVED ALLEY
8	"	"	"	"
9	"	"	DIRT	"
10	"	"	"	"
11	"	"	DIRT-A.C. PAV	A.C. @ "F" ST.
12	"	"	DIRT	"
13	"	39TH ST.	CL "D" CONC	"
14	10"	"J" ST	AC PAV-DIRT	A.C. -41ST TO MORRISON
15	8"	"J" ST-43RD ST	CL "D" CONC.	"
16	"	"K" ST	"	"
17	"	44TH-GAVIN	"	"
18	"	CARLOS ST	"	"
19	"	41ST-GAVIN	"	"
20	"	ALLEY	"	"

WORK TO BE DONE

THE IMPROVEMENTS CONSIST OF THE FOLLOWING WORK TO BE DONE ACCORDING TO THESE PLANS AND THE FOLLOWING SPECIFICATIONS AND STANDARD DRAWINGS OF THE CITY OF SAN DIEGO.

IMPROVEMENTS	STANDARD DRAWINGS	LEGEND
SEWER MAINS	S-1	8" OR 10" V.C.
SEWER MANHOLES	S-8, M-23, M-6	MANHOLE
NEW SEWER LATERAL	S-22	
CONNECTION OF EXISTING SEWER LATERAL		
HOUSE CONNECTION ON PRIVATE PROPERTY		
EXISTING WORK	P-1	
CONCRETE CRADLE	S-3	
FOUNDATION ROCK	A5 DIRECTED BY THE ENGINEER	
ADDITIONAL CLASS "A" BACKFILL	A5 DIRECTED BY THE ENGINEER	
IMPORTED CLASS "D" BACKFILL	A5 DIRECTED BY THE ENGINEER	
SEWER MAIN DROP CONNECTION	S-20	

SPECIFICATIONS

STANDARD SPECIFICATIONS-DOCUMENT NO 727731 FILED 4-14-69

SPECIAL SPECIFICATION NO. 2584

SPECIAL TRAFFIC REQUIREMENTS:
MAINTAIN 1 LANE IN EACH DIRECTION ON MARKET ST. BETWEEN 3:30 P.M. AND 8 A.M. ONE LANE WITH FLAGMAN MAY BE USED BETWEEN 8 A.M. AND 3:30 P.M.

REPLACE ANY CITY CONTROL POINTS LOST DURING CONSTRUCTION.
NOTE: MARKET STREET TRAFFIC DETOURED DURING CONSTRUCTION.

STANDARD DRAWINGS

VOLUME 68-1, DOCUMENT NO 726180 FILED NOVEMBER 20, 1968.

REFERENCE DRAWINGS

SEWER: 372-L, 3723-L, 4372-MISC, 8837-L, 14539-L, 11022-S-D, 327-D, 1385-B

WATER 5142-W, 6825-D

FIELD NOTES: SEWER GROUP 5, PHASE I, GREENWOOD AREA
W.O. 47165-63671, SHTS. 1-21
FIELD NOTES ALLEY IN BLK 7, IMPERIAL HTS., FROM 38TH ST. TO 39TH ST. BETWEEN FLORENCE AND LOGAN
W.O. 33760, SHTS. 1-6

NOTES

BEFORE EXCAVATION FOR THIS CONTRACT, THE CONTRACTOR SHALL VERIFY THE LOCATION OF UNDERGROUND UTILITIES. THE LOCATION OF ANY UNDERGROUND UTILITY PIPES OR STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF THE AVAILABLE RECORDS. TO THE BEST OF OUR KNOWLEDGE THERE ARE NO OTHER EXISTING UTILITIES EXCEPT AS SHOWN ON THESE PLANS.

THE CONTRACTOR SHALL TAKE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN HEREON AND/OR ANY OTHER EXISTING LINES NOT ON RECORD OR NOT SHOWN ON THESE PLANS.

THE CONTRACTOR SHALL NOTIFY THE FOLLOWING AGENCIES PRIOR TO STARTING WORK NEAR THEIR FACILITIES AND SHALL COORDINATE HIS WORK WITH THEIR REPRESENTATIVES:

SAN DIEGO GAS & ELECTRIC CO. PHONE 232-4252, EXT 1658
PACIFIC TELEPHONE CO. 298-0595
SAN DIEGO UTILITY DEPARTMENT 236-5650
BLDG. & ELECT. 236-5505
FIRE ALARM 234-6154

EXISTING SEWER MAINS & MANHOLES IN THE LOCATION OF THE NEW CONSTRUCTION TO BE REMOVED, EXCEPT AS NOTED.

THE CONTRACTOR SHALL SCHEDULE WORK TO GIVE PRIORITY TO ALLEY BLOCK 7, IMPERIAL HEIGHTS (SHEET 20)

SEWER MAIN RETIREMENT

LENGTH	TYPE	DRAWING NO	DATE INSTALLED
301'	8" CONC	86-41	1928
5376'	6" CONC	86-41	1928
215'	8" V.C.	8837-D	1951
574'	10" CONC	3722-L	1928
110'	6" CONC	3726-L	1928
1102'	8" CONC.	3723-3727-L	1928
96'	8" V.C.	NAVY	
1050'	6" V.C.	"	
560'	6" CONC	327-D	1925

SCALE 1"=200'

DESIGN ENGINEER-Charles R. Crull
MUNICIPAL ENGINEERS INC. 239-8171
235 BROADWAY SAN DIEGO, CALIF. 92101

JOB NO 5780

SEWER GROUP 5, PHASE I GREENWOOD AREA			
APPROVALS		CITY OF SAN DIEGO, CALIFORNIA	
DEPARTMENTAL	ENG. DEPT. DIVISION OR SECTION	UTILITIES DEPARTMENT	NO. 47165
PLANNING	CONST. INSPECTION	SHEET 1 OF 20 SHEETS	NO. 63671
PROPERTY	ELECTRICAL	UTILITIES DIRECTOR	DATE 2/25/71
PUBLIC WORKS	FIELD CHECK	DATE 2/25/71	DATE 2/25/71
RECREATION	CONCRETE AND REPAIRS	DATE 2/25/71	DATE 2/25/71
UTILITIES	HIGHWAYS	DATE 2/25/71	DATE 2/25/71
STRUCTURAL	MONUMENTS	DATE 2/25/71	DATE 2/25/71
TRAFFIC	SEWERAGE	DATE 2/25/71	DATE 2/25/71
WATER	STREET ACTIONS	DATE 2/25/71	DATE 2/25/71
DESCRIPTION		BY	APPROVED
ORIGINAL			
CONTROL CERTIFICATION			
"AS-BUILT"		RWM	DATE 2/25/71
CONTRACTOR: CASTILLO		DATE STARTED: 12/1/70	DATE COMPLETED: 2/25/71
INSPECTOR: STERLING GREEN			
		198-1734	13743-1 -D

AS BUILT

0 1 2 3 4 IN.